



City of Wilton Manors
Finance Department
2020 Wilton Drive
Wilton Manors, FL 33305

Phone (954) 390-2171
Fax (954)390-2199
www.wiltonmanors.com

Addendum No. 1

ITB for NE 23rd Drive Parking Lot Construction
Addendum Release Date December 22, 2016

ITB # 2016-02

ITB Due Date/Time: January 03, 2017, 2:30 p.m. Eastern Standard Time

Submit To: City Clerk
City of Wilton Manors
2020 Wilton Drive
Wilton Manors, Florida 33305

The purpose of this Addendum is to answer questions received from potential proposers. These are questions that were received prior to the published deadline for questions of December 19, 2016.

IMPORTANT NOTE – the following is added to ITB # 2016-02. It is the Proposer’s responsibility to use the revised information when preparing the response.

1. Q: What is the engineer’s estimate?
A: \$ 240,000.00

2. Q: Pay Item # 23 F&I Bike Rack – Provide specs, vendor and model number of the bike rack.
A: The Contractor will not be responsible for providing or installing the bike rack, the trash receptacle, the pet waste station, or the parking paystation. All of these items will be provided and installed by the City on the flat concrete slab. A revised bid sheet is included in this addendum to take this change into account.

3. Q: Pay Item # 24 F&I Trash Receptacle – Provide specs, vendor and model number of the trash receptacle.
A: The Contractor will not be responsible for providing or installing the bike rack, the trash receptacle, the pet waste station, or the parking paystation. All of these items will be provided and installed by the City on the flat concrete slab. A revised bid sheet is included in this addendum to take this change into account.

4. Q: Pay Item # 25 F&I Pole Mounted Dog Waste Bag Dispenser – Provide specs, vendor and model number of the dog waste station.
A: The Contractor will not be responsible for providing or installing the bike rack, the trash receptacle, the pet waste station, or the parking paystation. All of these items will be provided and installed by the City on the flat concrete slab. A revised bid sheet is included in this addendum to take this change into account.



City of Wilton Manors
Finance Department
2020 Wilton Drive
Wilton Manors, FL 33305

Phone (954) 390-2171
Fax (954)390-2199
www.wiltonmanors.com

5. Q: Was not able to acquire drawings for the wall form Cad Details as referenced in the drawings.
A: The CAD version of the detail drawing is not required.

6. Q: Is an office trailer required?
A: No.

7. Q: Are monthly photos required for the project?
A: No.

8. Q: Please provide the 6' concrete panel wall footer design.
A: Please refer to Concrete Panel Wall detail on Sheet PGDD-1.

9. Q: Please provide specs and manufacture for Pay Station base connection.
A: The Contractor will not be responsible for providing or installing the bike rack, the trash receptacle, the pet waste station, or the parking paystation. All of these items will be provided and installed by the City on the flat concrete slab. A revised bid sheet is included in this addendum to take this change into account.

End of Addendum # 1

CITY OF WILTON MANORS
NE 23rd DRIVE PARKING LOT

BID SCHEDULE

<u>Item</u>	<u>GENERAL</u>	<u>Quantity</u>	<u>Unit</u>	<u>Unit Price</u>	<u>Amount</u>
1	Mobilization	1	LS	\$ _____	\$ _____
2	Maintenance of Traffic	1	LS	\$ _____	\$ _____
3	Bonds and Insurance	1	LS	\$ _____	\$ _____
4	Permit Allowance	1	AL	\$ 5,000.00	\$ 5,000.00
5	Construction Contingency	1	AL	\$ 10,000.00	\$ 10,000.00
6	Indemnification	1	LS	\$ 25.00	\$ 25.00
GENERAL SUBTOTAL					\$ _____
<u>DRAINAGE</u>					
7	Furnish and Install Drainage Catch Basin (48" Round) w/ Frame/Grate	3	EA	\$ _____	\$ _____
8	Furnish and Install 18" RCP Drainage Pipe	20	LF	\$ _____	\$ _____
9	Furnish and Install 18" RCP Exfiltration Trench	65	LF	\$ _____	\$ _____
10	Furnish and Install Pollution Retardant Baffle	4	EA	\$ _____	\$ _____
DRAINAGE SUBTOTAL					\$ _____
<u>ROADWAY</u>					
11	Remove and Dispose of Existing Asphalt Pavement	25	SY	\$ _____	\$ _____
12	Clear and Grade Site Area	1,250	SY	\$ _____	\$ _____
13	Compaction of Subgrade (12")	955	SY	\$ _____	\$ _____
14	Furnish and Install Limerock Base (8")	955	SY	\$ _____	\$ _____
15	Furnish and Install Asphalt Pavement - Type S-1 (1-1/4")	955	SY	\$ _____	\$ _____
16	Furnish and Install Asphalt Pavement - Type S-III (3/4")	955	SY	\$ _____	\$ _____
17	Furnish and Install Concrete Type D Curb	620	LF	\$ _____	\$ _____
18	Furnish and Install Concrete Drop Curb (at curb ramps)	40	LF	\$ _____	\$ _____
19	Furnish and Install Concrete Sidewalk (4" Thickness)	165	SY	\$ _____	\$ _____
ROADWAY SUBTOTAL					\$ _____

HARDSCAPE

20	Remove Existing 6' Wood Fence	151	LF	\$ _____	\$ _____
21	Furnish and Install 6' Concrete Panel Wall with Footers	188	LF	\$ _____	\$ _____

HARDSCAPE SUBTOTAL

\$ _____

PAVEMENT MARKINGS AND SIGNAGE

22	Furnish and Place 6" Thermoplastic Striping (solid line)	420	LF	\$ _____	\$ _____
23	Furnish and Place 24" Thermoplastic Striping (stop bars)	24	LF	\$ _____	\$ _____
24	Furnish and Place Thermoplastic Pavement Symbols	4	EA	\$ _____	\$ _____
25	Furnish and Install Pedestrian Detectable Warnings for ADA Ramps	7	EA	\$ _____	\$ _____
26	Furnish and Install Sign with Post	3	EA	\$ _____	\$ _____
27	Furnish and Install Wheel Stops	22	EA	\$ _____	\$ _____

PAVEMENT MARKINGS AND SIGNAGE SUBTOTAL

\$ _____

LANDSCAPE

28	Furnish and Install Relocated Sabal palmetto, Cabbage Palm, 'Varies'	2	EA	\$ _____	\$ _____
29	Furnish and Install Conocarpus erectus, Green Buttonwood (B&B, 12' H	7	EA	\$ _____	\$ _____
30	Furnish and Install Conocarpus erectus 'Sericeus', Silver Buttonwood (B	8	EA	\$ _____	\$ _____
31	Furnish and Install Senna surattensis, Glaucous Cassia (B&B, 10' HT,	5	EA	\$ _____	\$ _____
32	Furnish and Install Chrysobalanus icaco 'Horizontalis', Horizontal Cocoç	240	EA	\$ _____	\$ _____
33	Furnish and Install Muhlenbergia capillaris, Pink Muhly (24" HT, Full, 24	196	EA	\$ _____	\$ _____
34	Furnish and Install Zamia pumila, Coontie Palm (24" HT, Full, 30" SP. C	42	EA	\$ _____	\$ _____
35	Furnish and Install Paspalum notatum, Bahia Grass (Full sod)	200	SY	\$ _____	\$ _____
36	Protect Existing Tree	1	EA	\$ _____	\$ _____

LANDSCAPE SUBTOTAL

\$ _____

IRRIGATION

37	Furnish and Install Turf Spray: Toro 570Z-6P-XF-COM-PC MPR, 12'	1	LS	\$ _____	\$ _____
38	Furnish and Install Turf Strip Spray: Toro 570Z-6P-XF-COM-PC MPR	1	LS	\$ _____	\$ _____
39	Furnish and Install Dripline: Toro RGP-412 (18)	1	LS	\$ _____	\$ _____
40	Furnish and Install Remote Control Valve: Toro P-220	1	LS	\$ _____	\$ _____
41	Furnish and Install Pressure Vaccum Breaker: Zurn 720A	1	LS	\$ _____	\$ _____
42	Furnish and Install Wall Mount Controller: Toro TMCE-424-OD-4H	1	LS	\$ _____	\$ _____
43	Furnish and Install Wired Rain Sensor	1	LS	\$ _____	\$ _____
44	Furnish and Install Water Meter (1") with Meter Box	1	LS	\$ _____	\$ _____
45	Furnish and Install Lateral Line: PVC SCH. 40	1	LS	\$ _____	\$ _____
46	Furnish and Install Mainline: PVC SCH. 40	1	LS	\$ _____	\$ _____
47	Furnish and Install Pipe Sleeve: PVC SCH. 40	1	LS	\$ _____	\$ _____

IRRIGATION SUBTOTAL

\$ _____

ELECTRICAL

48	Furnish and Install Light Fixture/Pole/Footer (Complete)	9	EA	\$ _____	\$ _____
49	Furnish and Install UG Cable 5#8	1	LS	\$ _____	\$ _____
50	Furnish and Install PVC Conduit (2")	1	LS	\$ _____	\$ _____
51	Furnish and Install Panelboard (240 V 3R 100A 1Ph)	1	LS	\$ _____	\$ _____
52	Furnish and Install Lighting Contactor (100A 3P)	1	LS	\$ _____	\$ _____
53	Furnish and Install Photocell	1	LS	\$ _____	\$ _____
54	Furnish and Install Meter and Panelboard Support	1	LS	\$ _____	\$ _____
55	Furnish and Install Disconnect Switch (100A 2P)	1	LS	\$ _____	\$ _____

ELECTRICAL SUBTOTAL

\$ _____

TOTAL BASE AMOUNT

\$ _____