Island City Park Preserve Physical Fitness

Exercise Stations

Request for Proposals

ADDENDUM 2

JUNE 17, 2014

Addendum #2 to City of Wilton Manors RFP No. 2014-003

Island City Park Preserve Physical Fitness Exercise Stations

39TH Year CDBG – RFP Questions & Answers – Mandatory Bid Meeting / June 16, 2014

General Introduction: Statement of Intent / Clarification

1. The **"Shade Structure – Installation Video"** will not be required, but, it is recommended to provide, if available, for the future maintenance and canopy re-moveable.
2. **Important Notice: Section "E" Department of Housing & Urban Development** / Boiler Plate: Design / Build Contractor shall make sure all documents are fully completed. In particular, review Page 3 of 38; make sure to complete Page # 12; and complete either Page # 15 OR Page # 16. Check to make sure all appropriate forms are completed.
3. Reminder, Design / Build Contractor to provide **required Bid Bond**.
4. **General Construction / Existing 6" Sanitary Sewer Line:** Design / Build Contractor has been previously provided an approximate location plan of the existing 6" sanitary sewer line. Contractor shall coordinate with the City to maintain the safety and protection of this underground sewer line during excavation.
5. **Site Plan** was prepared from a previous Architect's Site Development Plan. Additional, on site taping and measurements were developed to create the Present Plan.
6. **Slope / Grading of the Fitness Equipment Area**: The cross-section detail of the fitness equipment area indicates the design intent of approximately 1 to 1 ½ % slope towards the existing driveway. However, during the initial construction, preliminary excavation and site stakeout, the City will consider using the concrete curb as 6" curb edge above grade towards the driveway side. However, this would reduce amount grading and fill. Any additional cost shall be included as part of curbing Item #5.

<u>Technical Specifications: Clarification on Questions / Comments</u>

7. Technical Specifications: **Shade Structure** – Engineering Data: Design / Build Contractor shall provide the required all engineer drawings, which will meet the latest code requirements. Presently, Shade structure shall be for Wind speed: Frame only 170 m.p.h. & Frame w/ canopy: 120 m.p.h.
8. Technical Specifications: **Shade Structure** – Clarification: Shade canopy color will be Medium (Royal Blue) similar color to existing shade canopy at Park. Post / Colors will be White. Prior to finalizing the Final Contract with the successful Design / Build Contractor, the City will determine final color selection (a standard color), which will be coordinated with the available Fitness Equipment color selected.
9. Technical Specifications: **Shade Structure** – Clarification: The Design / Build Contractor will have Manufacturer to provide the proper shade canopy fastening system, complete.

10. Technical Specifications: **Fitness Equipment**– Clarification: If the concrete deck surface (Alternate #3) is installed, the Design / Build Contractor will provide required drawings for review. The City's Building / Permit Department will determine if "surface mounting" method for the fitness equipment will meet code requirements after reviewing engineering details.
11. Technical Specifications: **Synthetic Turf**– Clarification: The Synthetic Turf surfacing and Enviro Fill was answered in Addendum # 1 / Answer # 4 & # 5. The Synthetic Turf surface is not intended as a "playground surface." Contractor to provide a clean, tight, and permanent surface with no seam fraying.